BRUHAT BANGALORE MAHANAGARA PALIKE

NAME OF WORK: Providing new borewlls and CC roads, drains developments in Rachenahalli and other adjusted layout

RATE ANALYSIS

Estimate Amount:- Rs 199.00 LAKHS

Sl No	Description.	Unit	Page	Item	Basic rate	Lift charges	Total	AW @ 6%	Total Rate	Add T.P (+)%	Final Rate.
2	Providing and laying in position plain cement concrete of Mix 1:3:6 with OPC @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @ 0.465cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM curing complete as per specifications. and as per the directions of the Engineer in charge	Cum	Pg No.13of KPWD S.R 2018-19	4.2	5650.24	-	5650.24	339.0144	5989.25	0.00	5989.25
3	Providing laying plain/ reinforced cement concrete for side Drains Using M20 nominal mix Concrete with OPC at 300kgs.With 20mm and Down size granite metal coarse aggregate at 0.69cum and fine aggregate at 0.43cum Machne mixed, well compacted for wall and Bottom including centering shuttering,cost of materials,HOM of Machinery.Curing Etc.,Complete Excluding cost of Steel as per morth MORTH specification and as per the directions of the Engineer in charge	Cum	Pg No.27of KPWD S.R 2018-19	37.59.2	7292.14	-	7292.14	437.5284	7729.67	0.00	7729.67
6	Providing and Fixing pre cast covering Slab 250mm thick made out of CC 1:2:4 and jelly 20mm Down size with steel reinforcement including form work,curing,including cost of alll materials, labour,hire charges of machinery, loading, unloading, lead and lift,transportation etc ,complete. and as per the directions of the Engineer in charge	Sqm	Data rate	-	5418.00	-	5418.00	0	5418.00	0.00	5418.00

Scanned by CamScanner

Sl No	Description.	Unit	Page	Item	Basic rate	Lift charges	Total	AW @ 6%	Total Rate	Add T.P (+)%	Final Rate.
E1	Providing and constructing load bearing wall with Solid Concrete blocks of size 400x150x200mm having block density more than 1800kg/m3 and minimum compressive strength of 4.00 N/mm2 conforming to IS 2185 (Part - I) - 2005 and constructed with CM 1:4 as per IS 2572:2005 including cost of all materials, labour, scaffolding and curing. usage charges of machinery etc complete as per specifications.	Sqm	Pg No.27of KPWD S.R 2018-19	5.26.2	962.00	-	962.00	57.72	1019.72	0.00	1019.72
E2	KSRB 4-1.6 ; Providing and laying in position plain cement concrete of Mix 1:2:4 with OPC @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregtes @ 0.53cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills. including cost of all materials, labour, HOM curing complete as per specifications. Specification No. KBS 4.1. 4.2. (P.No-13,I No-4.6)	Cum	Pg No.13of KPWD S.R 2018-19	4.60	5650.24	-	5650.24	339.01	5989.25	0.00	5989.25

30.07.2022

Asst Engineer

ಸಹಾಯಕ ಅಭಿಯರಂತರರು

ಕೃ.ಪ್ರ.ವಿ.ವಿ. ಬೆಂಗಳೂರುಮಹಾನಗರ ಉಪ ವಿಭಾಗ

Assistant Executive Engineer,
R.R. Nagar, Sub-Division,
KRIDL, BBMP, Bangalore

Assistant Executive Engineer

ಸಹಾಯಕ ಕಾರ್ಯನಿರ್ವಾಹಕ ಅಭಿಯಂತರರು

ಬ್ಯಾಟರಾಯನಪುರ ಉಪ ವಿಭಾಗ

ಬಿ.ಬಿ.ಎಂ.ಪಿ, ಬೆಂಗಳೂರು-೭೫

Executive Engineer

ಕಾರ್ಯ ಪಾಲಕ ಅಭಿಯಂತರರು

ಬ್ಯಾಟರಾಯನಪುರ ವಿಭಾಗ ಯಲಹಂಕ ವಲಯ

ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ ಬೆಂಗಳೂರು-560092.

	and stock piling at designated locations and disposal of dismantled	795194.00	0.00	72479.00	

Scanned by CamScanner